# ATTAR

## Advanced Technology Testing and Research

**ATTAR TEST REPORT NUMBER: 06/0745**

March 22, 2006                                             **Total Pages: 1**

## OIL-WET RAMP SLIP RESISTANCE                    Job No: M06/0745

| Prepared for: | Gerflor Australasia Pty Ltd<br>17 Cato St<br>HAWTHORN EAST, VIC 3123 |
|---|---|
| Attention: | Mr Michael Glover |
| Test Site: | ATTAR, Unit 27, 134 Springvale Road, Springvale. |
| Test Date: | 21 March 2006 |
| Manufacturer: | Gerflor |
| Test Specimen, Size & Quantity Received: | Taraflex Sport Design    (6381) Maple - Batch No: 26689A015, 3.5 x 1.5 m supplied, 1 off |
| Sampling & Direction of Testing: | Sampling conducted by client. Tested along grain pattern. |
| Test Personnel: | John Dimopoulos & Marcus Brache |
| Preparation: | As received, a 600 x 800 mm section cut and mounted on a 12 mm thick piece of chip board. |
| Joint Width: | N/A |
| Air Temperature: | 26°C |
| Test Standard: | AS/NZS 4586 - 2004 Slip resistance classification of new pedestrian surface materials – Appendix D. |
| Surface Structure : | Smooth |

| Classification Criteria:<br>(TABLE D3 in AS/NZS 4586- 2004) | Corrected Mean Overall Acceptance Angle | Slip Resistance Assessment Group |
|---|---|---|
| | 6° to 10° | R9 |
| | Over 10° to 19° | R10 |
| | Over 19° to 27° | R11 |
| | Over 27° to 35° | R12 |
| | Over 35° | R13 |

| Displacement Space: | Not Measured |
|---|---|
| Displacement Space Assessment Group: | N/A |
| Mean Overall Acceptance Angle: | 16.0° |
| Slip Resistance Assessment Group: | R10 |

These results apply only to the specimens tested and it is recommended that before selection of flooring or paving materials the effect of service conditions, including maintenance procedures and wear on their slip-resistance be checked.

**NOTE:  Any specimens supplied will be disposed of in two (2) months time, unless otherwise instructed.**

## ATTAR

John Dimopoulos BEng (Mech) Hons.,
Post.Grad.Dip.Man.
Principal Mechanical Engineer

SLIPTR060745