



# Gerflor USA Commercial Adhesive Chart

GERFLOR COMMERCIAL PRODUCTS																
ADHESIVE CHART - COVERAGE - MOISTURE LIMITS																
Adhesives	RH Limit (ASTM F2170)	CC Limit (ASTM F1869)	pH Limit	Size	Trowel notch	Coverage per Pail or Can of Adhesive	Mipolam, Taralay	Tarasafe & H2O	LVT: Creation, Continuum, SAGAZ	Mipolam Biocontrol ELS & ESD+	Mipolam Technic ELS & GTI Cleantech ELS	Mipolam Evo & Creation Evo	GTI, GTI MAX, Attraction, Creation Connect, Solid Clic & Clic	GTI MAX Cleantech Cleanroom	Linoleum	SPM Wall Panels
Gerfix NDT Tape	98%	15 lbs.	12	2.46' x 98.42' / 2" x 98.42'	None	250 sq ft	Green	Yellow	Green	Green	Green	Green	Green	Green	Red	Red
Gerfix TPS+ (acrylic)	95%	10 lbs.	11	4 US Gal.	1/32" x 1/16" x 1/32" 'U'	680 to 880 sq. ft./ pail	Green	Yellow	Green	Green	Green	Green	Green	Green	Red	Red
Gerfix Resilient Spray	95%	8 lbs.	11	21 oz. Can	None	150 to 167 sq. ft./ can	Green	Yellow	Green	Green	Green	Green	Green	Green	Red	Red
Gerfix LVT & Plank Spray	95%	8 lbs.	11	21 oz. Can	None	150 to 167 sq. ft./ can	Green	Yellow	Green	Green	Green	Green	Green	Green	Red	Red
Gerflor T-111 (polyurethane)	95%	8 lbs.	11	1.9 US Gal.	1/32" x 1/16" x 1/32" 'U'	320 to 420 sq. ft./ pail	Yellow	Wet Areas	Yellow	Red	Red	Yellow	Yellow	Yellow	Red	Red
Gerflor T-111 (polyurethane)	95%	8 lbs.	11	1.9 US Gal.	3/32" x 3/32" x 3/32" 'V'	135 to 150 sq. ft./ pail	Red	Red	Red	Red	Red	Red	Red	Red	Red	Non-porous
Gerfix 313 Linoleum Adhesive	90%	8 lbs.	11	4 US Gal.	1/16" x 1/16" x 1/16" Square	400 to 500 sq. ft./ pail	Red	Red	Red	Red	Red	Red	Red	Red	Green	Red
Gerflor 505 SPM Wall Adhesive	N/A	N/A	N/A	4 US Gal.	3/32" x 3/32" x 3/32" 'V'	280 to 320 sq. ft./ pail	Red	Red	Red	Red	Red	Red	Red	Red	Red	Porous
Gerfix 196 (2-part Hybrid Acrylic)	98%	15 lbs	12	2.5 US Gal.	1/32" x 1/16" x 1/32" 'U'	425 to 550 sq. ft./ pail	Green	Yellow	Green	Green	Green	Green	Yellow	Green	Red	Yellow
Gerfix 196 (2-part Hybrid Acrylic)	98%	15 lbs	12	2.5 US Gal.	1/16" x 1/16" x 1/16" Square	200 to 250 sq. ft./ pail	Red	Red	Red	Red	Red	Red	Red	Red	Green	Red

**Gerflor's Position on Moisture Testing**

- Gerflor requires concrete slab moisture testing for any adhesive that is not rated for 100% RH
- Gerflor recognizes 2 methods to measure the moisture in a concrete slab: ASTM F2170 (RH) test and ASTM F1869 Calcium Chloride (CC) test
- It is always recommended to conduct both tests, and all tests need to meet the stated moisture limits
- If only one type of test is performed, Gerflor prefers the ASTM F2170 test method
- If Gerflor conducts an inspection on a moisture-related failure, we reserve the right to perform both tests

Color Legend
Green = Approved
Yellow = Needs Technical approval
Red = NOT approved

Gerflor USA  
 750 Veterans Parkway  
 Bolingbrook, IL 60440  
 (877) 437-3567  
 Email: info@gerflorusa.com  
 Website: gerflorusa.com

Updated: May 1, 2026



## Gerflor USA Sport Products Adhesive Chart

GERFLOR SPORT PRODUCTS				ADHESIVE CHART - COVERAGE - MOISTURE LIMITS									
Adhesives	RH Limit (ASTM F2170)	CC Limit (ASTM F1869)	pH Limit	Size	Trowel notch	Coverage per pail or can of adhesive	Recreation Range	Taraflex Range	Sport M Comfort	Taraflex Dry-Tex	Isolsport	Vinyl BleacherBlok® SV	Surface to Bleacher Blok
Gerfix TPS+ (acrylic)	95%	10 lbs.	11	4 US Gal.	1/32" x 1/16" x 1/32" 'U'	680 to 880 sq. ft./ pail							
Gerfix Resilient Spray	95%	8 lbs.	11	21 oz. can	none	150 to 167 sq.ft./ can							
Gerflor T-111 (polyurethane)	95%	8 lbs.	11	1.9 US Gal.	1/32" x 1/16" x 1/32" 'U'	320 to 420 sq. ft./ pail							
Gerpur (urethane)	100%	25 lbs.	14	2.5 US Gal.	1/16" x 1/16" x 1/16" Square	200 to 250 sq. ft./ pail							

### Gerflor's Position on Moisture Testing

- Gerflor requires concrete slab moisture testing for any adhesive that is not rated for 100% RH
- Gerflor recognizes 2 methods to measure the moisture in a concrete slab: ASTM F2170 (RH) test and ASTM F1869 Calcium Chloride(CC) test
- It is always recommended to conduct both tests, and all tests need to meet the stated moisture limits
- If only one type of test is performed, Gerflor prefers the ASTM F2170 test method
- If Gerflor conducts an inspection on a moisture-related failure, we reserve the right to perform both tests

### Color Legend

	Green = Approved
	Yellow = Needs Technical approval
	Red = NOT approved



Products	Products										
	Gerfix NDT Tape	Gerfix TPS+	Gerfix Spray	Gerfix LVT Spray	Gerflor T-111	Gerpur	Gerfix 313	Gerfix 505	Gerfix 196	Gerfix 100	
Creation WellPoint, Creation GuidePoint, Creation GrovePoint, & SAGA <sup>2</sup>	X	X		X	NTP				X		NTP = Needs Technical Approval
Creation Clic 28, Creation 70 Clic & Creation 22 Solid Clic		NTP		X	NTP				NTP		
DLW Linoleum							X		X		
Mipolam BioControl EL5 & ESD+	X	X	X								
Mipolam Technic EL5	X	X		X							
GTI MAX Connect, Attraction, Creation Connect, GTI PURE Connect	X	NTP		X	NTP				NTP		
GTI MAX Cleantech Cleanroom	X	X		X	NTP				X		
GTI Cleantech ESD	X	X		X							
Mipolam Affinity	X	X	X		X				X		
Mipolam Biocontrol Performance	X	X	X		X				X		
Mipolam Biocontrol Clean	X	X	X		X				X		
Mipolam Elegance	X	X	X		X				X		
Mipolam Symbioz <sup>1</sup>	X	X	X		X				X		
Mipolam Troplan	X	X	X		X				X		
Mipolam Planet	X	X	X		X				X		
Mipolam Evo & Creation Evo	X				NTP				X		
Taralay Impression	X	X	X		X				X		
Taralay Premium	X	X	X		X				X		
Mipolam SPM Wall Panels					X		X				
Taraflex Multi-Use 6.2, Sport M Plus & Sport M Performance		X	X		X				X		
Recreation 45, 60 & 85		X	X						X		
Recreation & Taraflex Surface					X						
Over Isolsport (Taraflex Multi-Use 6.2, Sport M Plus & Performance)					NTP				X		
Taraflex Sport M Plus Dry-Tex & Sport M Performance Dry-Tex		NTP	NTP			X			NTP		
Vinyl BleacherBlok® SV (Taraflex & Recreation)					X					X	
Taraflex Sport M Comfort									X		
Tarasafe Ultra & H2O	NTP	NTP	NTP		X				NTP		

	<b>ASTM F1869 Calcium Chloride (CaCl)</b>	<b>ASTM F2170 Relative Humidity Test (RH)</b>
<b>Installation:</b>	Three tests for the 1st 1000 sq.ft. One additional test for each 1000 sq. ft. thereafter	Three tests for the 1st 1000 sq.ft. One additional test for each 1000 sq. ft. thereafter
<b>Exposure Time</b>	Minimum of 60 hours and a maximum of 72 hours	72 hours for the first tests. Subsequent test must stabilize with no drift on meter in a 5 minute period per ASTM F 2170
<b>Use:</b>	Moisture Vapor escaping from concrete and pH test	Relative humidity in the concrete
<b>Test Range:</b>	0.00 to 30.00 lbs	0 to 100% Relative Humidity
<b>Plus:</b>	Give an actual reading of water vapor escaping from the concrete slab	Give an actual reading of the relative humidity of the concrete slab
<b>Recommendation</b>	<b>Test substrate using both tests RH and CaCl. Should you use only one, RH testing is the preferred method</b>	